



VTC Room

P/N VTCMODSEC1000.1

VTC Room:

Facility modifications shall be limited to fabricating a "room within a room". The room's perimeter walls shall be sound insulated to STC-45 specifications. The room shall be outfitted with sound absorbing ceiling tile, sound absorbing wall treatments, moldings, carpet and solid wood doors. All necessary conduit, ductwork, wiring etc., that interconnects the facility equipment shall be included in the design. Any electrical work in the design shall abide by Local, and National Electrical Codes (NEC), regulations, and restrictions. Facility modifications shall not include asbestos removal nor slab-to-slab (bearing) wall fabrication or removal.

SIGCOM shall provide any or all of the following based on the room design and the results of the site survey.

- Provide limited room demolition preparation (removal of existing lighting fixtures, suspended ceiling, carpet, wall coverings, non-load bearing walls, not to include asbestos removal).
- HVAC systems and components.
- Fabricate Sound Transmission Coefficient (STC) 45 dB walls, which generally provides a sound barrier up to SECRET conference.
- Provide and install attractive, color coordinated, sound soak panels with base, chair and crown molding.
- Provide and install suspended, acoustic paneled ceiling and overhead fluorescent angled lighting.
- Provide and install industrial-type carpet.

4230 Beechwood Drive, Greensboro, NC 27410, info@sigcom.net
Phone 336-547-9700, Fax 336-547-1449

Contents Copyright 2003 SIGCOM, All Rights Reserved

<http://www.sigcom.net/commpricelist/commpricelist.htm>